

PBX : 2788618
: 2788619
G.M.(Direct) : 2788612
Fax : 2788616
E-mail : Vizag dccb @ rediff mail.com



The Dist. Co-operative Central Bank Ltd.,
N.T.R. Sahakara Bhawan, D.No. 58-14-57/1, Mairipalem VUDA Layout,
NH-5 Road, N.A.D. (Post), Visakhapatnam - 530 009.

వి జిల్లా సహకార కేంద్ర బ్యాంకు లిమిటెడ్

ఎన్.టి.ఆర్. సహకార భవన్, డోర్ నెం.: 58-14-57/1, మర్రిపాలెం ఉదా లే అవుట్,
యన్.హెచ్.-5 రోడ్, యన్.ఎ.డి. (పోస్ట్), విశాఖపట్నం - 530 009.

Ref: DEV/Notification/2026-27

Date: 05.05.2026

Sealed quotations are invited for Dismantling of Existing Lift and Civil & Electrical Works for Installation of New Lift

Sealed quotations are hereby invited from experienced and eligible contractors/agencies for carrying out the work of dismantling the existing lift and executing associated civil & Electrical works required for the installation of a new lift at Bank Central office.

Scope of Work:

- Safe dismantling and removal of existing lift equipment and structure.

Civil Work:

1. Shaft inside Bracket chipping & re-finish.
2. All landing call box fixtures cutting to be done & re-fixing the new LOP box.
3. Head room, shaft inside white wash coat to be provide.
4. Head room, shaft inside ISMB's to be provide for load shifting reg.
5. LIFT materials kept regards lockable store room required.
6. Scaffolding to be provided.
7. Old materials dis mantle work to be provided and shifting to be done by client scope.
8. All floors Entrance walls to be prepare as per GAD.
9. PIT INSIDE Buffer blocks to be provided and floor finish required as per GAD.
10. SAP panel cut out required in Top floor area.
11. Emergency exit window to be provided in Head room area.
12. Door frame surroundings cladding work to be provided.

Electrical Work :

1. Head room Electrical incoming panel to be replaced with proper rating RCCB & MCE recommendation.
2. Head room lighting arrangement to be provide.
3. Shaft lighting to be Provided with Switch boards.
4. Earthing 8 Guage Copper wires 2 nos to be provided from Earth pit to top floor MCB box.

5. 8 way box with MCB's to be provided (16 A 4 POLE-1 NO,10A 2 POLE-1 NO,2 POLE 6A-1 NO)

Submission Details:

- Sealed quotations must be submitted on or before: **11.05.2026** before 5.00pm
- Quotations should include detailed cost estimates, timelines, and terms & conditions
- The envelope should be clearly marked: *“Quotation for Lift Dismantling and Civil Works & Electrical works”*
- **Contact details: Phn.no. Development Section-9963607778**

Sealed quotations should be handed over directly to the address mentioned below:

0

To
The Chief Executive Officer,
The District Co operative Central Bank Ltd., Visakhapatnam.
N.T.R Sahakara Bhavan,
D.No:55-14/57/1,
Marripalem VUDA Layout,
NH-16,N.A.D,
Visakhapatnam-530009

Sd/-
Chief Executive Officer